

SEQUENCE OF OPERATION

1. Lighting auto On to 50% and controlled receptacles auto On when occupancy detected.
2. Manual On/Off lighting with wall switch occupancy sensor.
3. Auto off all lighting and controlled receptacles within 20 minutes of occupants leaving.

Note: Diagram is typical for space type. Provide proper quantity and type of occupancy sensors, switches, room controllers, daylighting sensors, etc., per code requirement for each space..

