

SEQUENCE OF OPERATION

1. Each 600 sq ft lighting zone and receptacles on 100% when occupancy is detected.
2. Manual On/Off/Dim general lighting (a,b,c,d,e) with dimmer switches.
3. Lighting in primary (a) and secondary (b) daylight zones will continuously dim based on daylight contribution to maintain a consistent FC at task level.
4. Lighting auto 50% off within 20 minutes of occupants leaving each zone
5. All lighting and receptacles 100% off at end of business day via time clock.

Note: Diagram is typical for space type. Provide proper quantity and type of occupancy sensors, switches, room controllers, daylighting sensors, etc., per code requirement for each space.

