

## SEQUENCE OF OPERATION

1. Lighting (a) auto On to 50% and controlled receptacles auto On when occupancy detected.
2. Manual On/Off/Dim general lighting (a) with dimmer switch.
3. Manual On/Off/Dim control under cabinet lighting (b) with dimmer switch.
4. Auto off all lighting and controlled receptacles within 20 minutes of occupants leaving except for refrigerators and water dispensers, **Exception 1 (a)**

Note: Diagram is typical for space type. Provide proper quantity and type of occupancy sensors, switches, room controllers, daylighting sensors, etc., per code requirement for each space.

