

SEQUENCE OF OPERATION

1. Lighting (a) auto On to 100% when occupancy detected. All lighting lowers to 50% within 20 minutes of occupants leaving area.
2. Manual On/Off/Dim general lighting (a) with dimmer switch.
3. Auto off all lighting at end of business day via time clock.

Note: Diagram is typical for space type. Provide proper quantity and type of occupancy sensors, switches, room controllers, daylighting sensors, etc., per code requirement for each space.

