

## SEQUENCE OF OPERATION

1. For each restroom independently, lighting auto On to 100% when occupancy detected.
2. Manual On/Off with local control key switch allowed to not be accessible to unauthorized personnel.
3. Auto off all lighting for each restroom independently within 20 minutes of occupants leaving.

Note: Diagram is typical for space type. Provide proper quantity and type of occupancy sensors, switches, room controllers, daylighting sensors, etc., per code requirement for each space.

